



6 - 854 Marion Street, Winnipeg, Manitoba, R2J 0K4  
Phone: (204) 233-1694 Fax: (204) 235-1579  
E-mail: eng\_tech@mts.net  
www.eng-tech.ca

December 02, 2016

File No. 16-035-01

WSP Canada Inc.  
1600 Buffalo Place,  
Winnipeg, MB  
R3T 6B8

**ATTENTION:** Jason Bunn

**RE:**            Hydraulic Conductivity Test Results, Brightstone Colony

ENG-TECH Consulting Limited (ENG-TECH) received the three (3) Shelby tube samples from the above site, and two (2) samples were extracted on November 18, 2016 and selected for hydraulic conductivity testing by MB Sustainable Development.

ENG-TECH prepared the samples labelled ST1 and ST3 for testing in accordance with ASTM D5084-03, *Standard Test Method for Measurement of Hydraulic Conductivity of Saturated Porous Materials using a Flexible Wall Permeameter*. The final hydraulic conductivity values ( $k_{20}$ ) of  $2.5 \times 10^{-8}$  cm/sec and  $5.8 \times 10^{-9}$  cm/sec were obtained for the samples identified as ST1 and ST3, respectively. The hydraulic conductivity test data is outlined in Table 1, while the graphical representations of the hydraulic conductivity versus elapsed time are shown in Figures 1 and 2.

ENG-TECH trusts the above is all the information you require. If you have any questions, please contact the undersigned.

Sincerely,  
ENG-TECH Consulting Limited

A handwritten signature in black ink, appearing to read "Clark Hryhoruk".


Clark Hryhoruk, M.Sc., P.Eng.  
President, Geotechnical Engineer

CDH/pfpc

Attachments:    Table 1 – Hydraulic Conductivity Test Data  
                      Figure 1 – Hydraulic Conductivity Versus Elapsed Time (ST1)  
                      Figure 2 – Hydraulic Conductivity Versus Elapsed Time (ST3)

**TABLE 1  
HYDRAULIC CONDUCTIVITY TEST DATA  
BRIGHTSTONE COLONY**

<b>SAMPLE IDENTIFICATION</b>	<b>ST1</b>	<b>ST3</b>
<b>INITIAL VALUES</b>		
ENG-TECH Reference No.	16-035-01-4	16-035-01-5
Length of Sample in Tube (cm)	Approx. 23.0	Approx. 33.0
Length (cm)	6.39	6.71
Diameter (cm)	6.31	6.89
Area (cm <sup>2</sup> )	31.3	37.3
Volume (cm <sup>3</sup> )	199.7	250.1
Water Content (%)	38.3	37.2
Bulk Dry Density (kg/m <sup>3</sup> )	1829	1842
Specific Gravity (G <sub>s</sub> ) (assumed)	2.68	2.68
Void Ratio	1.03	1.00
Degree of Saturation (%)	Approx.100	Approx.100
<b>FINAL VALUES</b>		
Length (cm)	6.52	6.89
Diameter (cm)	6.46	7.00
Area (cm <sup>2</sup> )	32.8	38.5
Volume (cm <sup>3</sup> )	213.6	265.0
Water Content (%)	46.1	48.2
Bulk Dry Density (kg/m <sup>3</sup> )	1753	1785
Specific Gravity (G <sub>s</sub> ) (assumed)	2.68	2.68
Void Ratio	1.23	1.23
Degree of Saturation (%)	100	100
<b>CONSOLIDATION PHASE</b>		
Confining Pressure (kPa)	103.4	103.4
Pore Water Pressure (kPa)	82.7	82.7
Effective Stress (kPa)	20.7	20.7
<b>PERMEATION PHASE</b>		
Confining Pressure (kPa)	103.4	103.4
Pore Water Pressure (kPa)	82.7	82.7
Effective Stress (kPa)	20.7	20.7
Hydraulic Gradient	17.2	16.3
Permeant Fluid	Distilled Water	Distilled Water
<b>HYDRAULIC CONDUCTIVITY at TEST TEMPERATURE OF 21 °C (cm/sec)</b>	$2.6 \times 10^{-8}$	$5.9 \times 10^{-9}$
<b>HYDRAULIC CONDUCTIVITY at TEMPERATURE OF 20 °C (K<sub>20</sub>) (cm/sec)</b>	$2.5 \times 10^{-8}$	$5.8 \times 10^{-9}$



6 - 854 Marion Street  
 Winnipeg, MB R2J 0K4  
 Phone: (204) 233-1694  
 Fax: (204) 235-1579

ENG. STAMP:



CLIENT:

WSP CANADA INC.

DATE:

DECEMBER 2016

DRAWN BY:

PFPC

FIGURE No.:

1

REV.:

PROJECT:

BRIGHTSTONE COLONY


FILE No.:

16-035-01

SCALE:

N/A

HYDRAULIC CONDUCTIVITY  
 VERSUS ELAPSED TIME  
 (ST1)



6 - 854 Marion Street  
 Winnipeg, MB R2J 0K4  
 Phone: (204) 233-1694  
 Fax: (204) 235-1579

ENG. STAMP:



CLIENT:

WSP CANADA INC.

DATE:

DECEMBER 2016

DRAWN BY:

PFPC

FIGURE No.:

2

REV.:

PROJECT:

BRIGHTSTONE COLONY

FILE No.:

16-035-01

SCALE:

N/A

HYDRAULIC CONDUCTIVITY  
 VERSUS ELAPSED TIME  
 (ST3)